

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 25 1963

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name E. K. EdmistonComplete Address: 501 First Nat'l Bldg., Wichita, KansasLease Name Simpson "A" Well No. # 2Location NE SE SW Sec. 29 Twp. 20 Rge. 12W(E) (W)County Barton Total Depth 3498Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Central Pipe Pulling Co.Address: 1416 Coolidge, Great Bend, Kansas License No. 459Operation Completed: Hour 11 AM Day 20 Month 3 Year 1963

The Above well was plugged as follows:

8 5/8" 258' Cwc.Sanded hole back to 3470' & dumped 3 sax cement with dump bailer.Pulled pipe. Mudded hole to 230'; set rock bridge & dumped 5 sax cementon bridge with dump bailer. Let set over-nite; bailed hole dry; dis-placed 20 sax cement. Mud to 40', set rock bridge, & displaced 10sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/26/63  
INV. NO. 6446-10Signed: John Truman  
Well Plugging Supervisor