

15.009.15639.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 501 1st., Nat'l Bldg., Wichita, Kansas

Lease Name Simpson "A" Well No. # 1

Location SE SE SW Sec. 29 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3530

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Inc.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11 AM Day 10 Month 3 Year 1964

The Above well was plugged as follows:

8 5/8" 250' Cwc.

Sanded hole back to 3470' & dumped 4 sax cement with dump bailer.

Pulled pipe. Set 10' rock bridge @ 240'; dumped 5 sax cement on bridge

with dump bailer. Let set over-nite; bailed hole dry; displaced 25 sax

cement. Mud to 40'; set rock bridge & displaced 10 sax cement, cementing

to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/17/64

INV. NO. 8791-W

Signed: Law T. ...
Well Plugging Supervisor