

15.009.08376.0000

Form CP-3
Rev. 6-26-62

46
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union Nat'l. Building
Wichita, Kansas

Lease Name Fischer Well No. # 1

Location SE/4 Sec. 31 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3265

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, Eldorado, Kansas License No. 547

Operation Completed: Hour 4 P.M. Day 13 Month 7 Year 1965

The Above well was plugged as follows:

10 3/4" 190' Cwc.

Set bottom plug @ 3150' & dumped 5 sax cement with dumpbailer.

Pulled pipe. Mudded hole to 185'; set rock bridge; displaced 5 sax cement

& 2 sax Calseal. Let set over night; bailed hole dry; displaced 30

sax cement. Mud to 40'; set rock bridge & displaced 15 sax cement,

cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/20/65

INV. NO. 1480-44