

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NE

SEC. 31 TWP. 20 RGE. 11

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Johnson

Operator Henderson Oil Co Address 8 502 Orpheum Bld Wich.

Field _____ County Barton

Total Depth 3442 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 295', circulated with cement.

Circulated hole with heavy rotary mud, pushed plug to
280', displaced 15 sax cement through drill pipe, heavy mud
to 40', set wood plug, 1/2 sack hulls and 10 sax cement to
bottom cellar.

PLUGGING
FILE NO. 31 T 20 R 11 W
PAGE 108 LINE 10

J. Edgar [Signature]
District Conservation Agent

Date 5-14-51 RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1951
CONSERVATION DIVISION
Wichita, Kansas