



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Jack Perkins of E. K. Edmiston has this

date requested permission to plug the following described well:

Mr. E. K. Edmiston guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 501 First Nat'l Bldg., Wichita, Kansas

Lease Name: Simpson "A" Well No. # 2

Location: NE SE SW Sec. 29 Twp. 20 Rge. 12W(E) (W)

County Barton Total Depth 3498 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Jack Perkins was instructed to plug the well as follows:

8 5/8" 258' Cwc.

Sanded hole back to 3470' & dumped 3 sax cement with  
dump bailer. Pulled pipe. Mudded hole to 230'; set rock  
bridge & dumped 5 sax cement on bridge with dump bailer.

Let set over-nite; bailed hole dry; displaced 20 sax  
cement. Mud to 40', set rock bridge, & displaced 10 sax  
cement, cementing to base of cellar.  
 Very truly yours,

*Don Truman*  
 Conservation Division Agent