



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

80

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Neighbors of ROCO Drlg., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Isern-Schultz Oil & Gas, Inc.

Complete Address: P O Box 486, Ellinwood, Kansas 67526

Lease Name: Jr Miller Well No. 1

Location: SW NE NE Sec. 35 Twp. 20S Rge. 11 KR (W)

County: Barton Total Depth: 3344'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated: _____

Mr. Neighbors was instructed to plug the well as follows:

Fill hole with mud and spot 60 sx cement at 540'.

Fill hole with mud and spot 30 sx cement at 240'.

Fill hole with mud to 40' and 1/2 sx hulls, plug, and 10 sx cem.

5 sx cement in rat hole.

257' of 8 5/8" surface casing cement circ.

Very truly yours,

Conservation Division Agent

RECEIVED
NOV 25 1980
11-25-80
WICHITA, KANSAS