



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C - G Drilling & G. A. Reed

Complete Address: 1107 Union Nat'l Bldg., Wichita, Kansas

Lease Name Miller Well No. 1

Location C SW NW Sec. 5 Twp. 20 Rge. 20 (E) (W) X

County Pawnee Total Depth 4391

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: C & G Drlg.

Address: Wichita, Ks. License No.

Operation Completed: Hour 5:45A Day 24 Month 9 Year 1968

The Above well was plugged as follows:

RTD 4391' 8 5/8 csg set at 278' cwc Cmt. Mat. 100 sc 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Mussey
Well Plugging Supervisor

INVOICED

DATE 9/26/68

INV. NO. 8525-W