



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JAN 10 1969

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drilling has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C- G Drlg. Co. and G. A. Reed

Complete Address: 1107 Union Natl. Bldg., Wichita, Ks.

Lease Name: Miller Well No. 2

Location: C SE NW Sec. 5 Twp. 20 Rge. 20 (E)(W) XX

County: Pawnee Total Depth 4390 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cement thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cement to base of cellar. Plug rat hole

with 2 sk cement.

Very truly yours,

[Signature]  
Conservation Division Agent