

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW-21W-SW

SEC. 3 ✓ TWP. 20 RGE. 11W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Kowalsky Kowalsky

Operator Bay Peter Corp Address Box #513 Chase-Kans.

Field _____ County Barton

Total Depth 3373 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 558 ft - Circulated with cement.
5 1/2 casing out at 3366 ft - 100 sacks of cement.
Same Wells Plug at 3145 ft - sand to 3100 ft -
blended 5 sacks of cement at 3100 ft - mud to
shot off & hulled the 5 1/2 casing - mud to 300 ft -
set rock bridge & 20 sacks of cement at 300 ft -
mud to 30 ft - Plug & 10 sacks of cement
at the surface - ✓

PLUGGING
FILE SEC 32720 R 121
BOOK PAGE 50 LINE 21

RECEIVED
STATE CORPORATION COMMISSION
OCT - 6 1952
CONSERVATION DIVISION
Wichita, Kansas

C. H. Stouck
District Conservation Agent
Date 10-3-52