

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C & G Drilling Co. & G. A. Reed

Complete Address: 1107 Union Nat'l Bldg., Wichita, Kansas

Lease Name Issac Well No. 3

Location C NE NE Sec. 5 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4365'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 8:30P Day 9 Month 10 Year 1969

The Above well was plugged as follows:

RTD 4365' 8 5/8 csg set at 278' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 10/14/69

INV. NO. 642-W