

STATE CORPORATION COMMISSION

15.145.20224.0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Inc.

Complete Address P. O. Box 352, Russell, Kansas 67665

Lease Name Smith Well No. 1

Location NE NW Sec. 21 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4286'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 11 A Day 19 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 4286' 8 5/8 csg set at 228' cwc: 140 sk.

5 1/2 csg set at 4282' cw 175 sk cmt.

Filled 5 1/2 csg with sand (4286-4250) dumped 4 sk cmt W/dump bailer. (4250-4220)

Cutoff and recovered 3170' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

and pumped 125 sk 50-50 poz 6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Red J. Manser
Well Plugging Supervisor

INVOICED

DATE 7/23/74

INV. NO. 9561-W