

15.009.11541.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name C. E. Denman

Complete Address: 3115 Broadway, Great Bend, Kansas

Lease Name Hagen Well No. # 1

Location SW NW NE Sec. 30 Twp. 20 Rge. 11 (E) (W)

County Barton Total Depth 3420

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Great Bend, Kansas License No. 462

Operation Completed: Hour 10:30AM Day 6 Month 12 Year 1963

The Above well was plugged as follows:

8 5/8" 245' Cwc.

Sanded hole back to 3400' & dumped 5 sx cement wh/dump bailer. Pulled
pipe. Mudded hole to 235'; set rock bridge; dumped 2 sx Cal-seal on
bridge. Let set over-nite. Bailed hole dry; displaced 25 sx cement. Mud
to 40'; set rock bridge & displaced 10 sx cement, cementing to base of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Truman
Well Plugging Supervisor

INVOICE
12/11/63
8253-w