



DISTRICT CONSERVATION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 1951
CONSERVATION DIVISION
Wichita, Kansas

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 107-43

LOCATION SE-NE-SE

SEC. 31 TWP. 20 RGE. 11-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease M. Fischer

Operator Sunray Oil Corp. Address Box #195 M. Bend - Kans.

Field _____ County Barton

Total Depth 3387 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 296 ft. Circulated with cement
7 casing set at 3383 ft. 150 sacks of cement
Lam. Wellb. Plug at 3306 ft. Plug sand back with
sand to 3260 ft. 5 sacks of cement at 3260 ft.
7 casing started at 1000 ft. Racked the 20" casing -
Filled hole with mud to 240 ft. Set Rock bridge
& 20 sacks of cement at 250 ft. mud to 30 ft. Plug
& 10 sacks of cement at the surface.
The West Supply Co - Plugging Contractors

PLUGGING
FILE SEC 31 T 20 R 11W
BOOK PAGE 107 LINE 43

C. H. Stovall
District Conservation Agent

Date 10-1-51