

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 10 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. C. E. Denman of C. E. Denman has this

date requested permission to plug the following described well:

Mr. Dean Wells guarantees payment of the plugging fee.

Operator's full Name: C. E. Denman

Complete Address: 3115 Broadway, Great Bend, Kansas

Lease Name: Hagen Well No. # 1

Location: SW NW NE Sec. 30 Twp. 20 Rge. 11 (E) (W)

County Barton Total Depth 3420 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Elmo Finch was instructed to plug the well as follows:

8 5/8" 245' Cwc.

Sanded hole back to 3400' & dumped 5. sx cement wh/dump  
bailer. Pulled pipe. Mudded hole to 235'; set rock bridge;  
dumped 2 sx Cal-seal on bridge. Let set over-nite. Bailed  
hole dry; displaced 25 sx cement. Mud to 40'; set rock  
bridge & displaced 10 sx cement, cementing to base of  
cellar.

Very truly yours,

Don Truman  
 Conservation Division Agent