



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED

STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) JAN 10 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Bolt of Mapco, Inc. has this
date requested permission to plug the following described well:

Mr. Mapco, Inc. guarantees payment of the plugging fee.

Operator's full Name: Mapco, Inc.

Complete Address: 1437 S. Boulder, Tulsa, Oklahoma

Lease Name: B. Hogen Well No. # 1

Location: C NE Sec. 28 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 1595 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Claude Bolt was instructed to plug the well as follows:

7" csg. 249' Cwc.

Circulated hole with heavy mud to 400', set plug, & displaced 40 sax
cement thru drill pipe. Mud to 240' & displaced 20 sax cement thru drill
pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with
Halliburton Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Lewis
Conservation Division Agent