



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Bryant "A" Well No. # 9

Location: CNL NW Sec. 25 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3264 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

10 3/4" 182' Cwc.

Sand back to 3230' & dumped 5 sax cement with dump bailer.

Pulled pipe to 300': circulated hole with mud. Pulled pipe

to 220'; displaced 30 sax cement, with pump truck. Pulled

remaining pipe; set rock bridge @ 35' & displaced 15 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent