

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 19-1

LOCATION CNW-SE-SW

SEC. 30 TWP. 20 RGE. 11 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease G. Soeken

Operator Drugh Petra Co. Address 907 Kennedy Bldg. Tulsa Okla.

Field County Barton

Total Depth 3406 Feet.

Plugging Contractor R. S. Pipe Pulling Co.

Plugging Contractor's License No. 1.

Address Ellenwood Kans. Box 192.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8" @ 338' C.W.C. Oil string 5 1/2" O.D
@ 3381' set w/ 200 sx Cem. Filled back with
sand to 3375' and dumped 5 sx Cem.
Shot off and pulled 5 1/2" casing. Filled hole
with mud to 300' set rock bridge and run
20 sx Cem. mud to 35' r. bridge and 10
sx of Cem to base of cellar.

PLUGGING
FILE SEC 30 TWP 20 R 11 W
BOOK PAGE 19 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1954
CONSERVATION DIVISION
WICHITA, KANSAS
4-12-1954

Warren H. Warner
District Conservation Agent

Date April 9, 1954