

DISTRICT CONSERVATION AGENT'S REPORT

*Handwritten mark resembling a stylized 'K' or arrow pointing up and right.*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW-SW-7W

SEC. 30 TWP. 20 RGE. 11

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Sochew

Operator Clada Oil & Gas Co. Inc. Address <sup>805</sup> U. N. B. Bldg - Wichita - Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3403 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 315 ft. Circulated with cement  
5/8 casing set at 3383 ft. Plugged back from bottom  
to 3140 ft with Mud - Low Wells Plus & chat -  
5 sacks of cement dumped in the 5/8 casing at 3140 ft  
shot off & pulled the 5/8 casing - Filled with mud to  
300 ft - Rock Bridges & 16 sacks of cement at 300 ft.  
Mud to 30 ft - Bridge & 10 sacks of cement at the surface

RECEIVED

PLUGGING  
FILE NO. 30-20-116  
BOOK PAGE 118 LINE 36

Conservation Div.

C. M. Stough  
District Conservation Agent

SEP 5 1949

Date

9-3-49

CORPORATION  
COMMISSION  
KANSAS

9-6-1949

*Handwritten 'X' mark.*