

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23530-00-00
Spot: SESESENE Sec/Twnshp/Rge: 36-13S-13W
2425 feet from N Section Line, 255 feet from E Section Line
Lease Name: HOLLAND UNIT B Well #: 1
County: RUSSELL Total Vertical Depth: 3415 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3412	1342	125 SX
SURF	8.625	433		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2018 10:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Cut casing at 1342' leaving 2070' of 5 1/2" casing in well.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2018 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/03/2018 - Sanded bottom of well to 2730' and pumped 5 sx cement on top.
04/04/2018 - Cut casing at 1342'. Pulled casing to 1150' and pumped 125 sx cement w/400 # hulls. Pulled casing to 830' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 50 sx cement w/100 # hulls. Pulled casing to 230' and pumped 30 sx cement. Circulated cement to the pit. POOH. Topped off cellar with 20 sx cement.

GPS: 38.87870 -098.70754

Perfs:

Top	Bot	Thru	Comments
3052	3058		LANSING 'C'

KCC WICHITA
APR 30 2018
RECEIVED

Remarks: QUALITY CEMENTING TICKET # 737

Plugged through: CSG

INVOICED

MAY 08 2018

District: 04

Signed _____

Ray A. Dinkel

(TECHNICIAN)

CM

APR 10 2018