

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21676-01-00  
Spot: NENWNWNE Sec/Twnshp/Rge: 34-33S-17W  
5386 feet from S Section Line, 2111 feet from E Section Line  
Lease Name: CARLISLE 3317 Well #: 2-27H  
County: COMANCHE Total Vertical Depth: 5183 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5086		WITH 50 SX CMT
COND	20	120		WITH 14 SX CMT
	11 9.625	964		WITH 530 SX CMT
	L1 4.5	9862		500 SX
PROD	7	5593	1764	WITH 225 SX CMT
SURF	13.375	365		WITH 420 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2018 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5086' WITH 50 SX CMT. PLUG AT 990' WITH 100 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2018 10:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5086'. CIRCULATED THE HOLE WITH 190 BBL MUD THEN SPOTTED 50 SX CMT ON TOP OF CIBP. 1ST PLUG AT 990' WITH 100 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8475	8830		
8048	8420		
7613	7950		
7118	7499		
6713	7030		
6158	6596		
5768	6090		
5323	5693		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD= 9862'

Plugged through: TBG

District: 01

RECEIVED  
APR - 9 2018  
KCC DODGE CITY

Signed



(TECHNICIAN)

INVOICE  
MAY 08 2018