

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-007-23965-01-00  
 Spot: SESWSWSE Sec/Twnshp/Rge: 3-35S-10W  
186 feet from S Section Line, 1989 feet from E Section Line  
 Lease Name: YAZEL Well #: 1-3H  
 County: BARBER Total Vertical Depth: 4755 feet

Operator License No.: 34192  
 Op Name: SANDRIDGE EXPLORATION AND PRO  
 Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		WITH 50 SX CMT
COND 20		106		WITH 10 SX CMT
L1 4.5		9161		
PROD 7		5272	1410	WITH 260 SX CMT
SURF 9.625		873		WITH 620 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2018 8:00 AM  
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
 Proposal Revd. from: JOEL FLORES Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4800' WITH 50 SX CMT. PLUG AT 900' WITH 100 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' TO SURFACE WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL  
 Date/Time Plugging Completed: 04/10/2018 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4800'. CIRCULATE HOLE WITH MUD & SPOT 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 900' WITH 100 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8175	8561		
7217	7602		
6738	7123		
6258	6622		
5779	6165		
5300	5685		
4696	8082		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD=9161'

Plugged through: TBG

District: 01

RECEIVED  
 APR 16 2018  
 KCC DODGE CITY

Signed Stephen J. Pfeifer  
 SA (TECHNICIAN)

INVOICED  
 MAY 9 8 2018