

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-24023-01-00
Spot: S2S2SESE Sec/Twnshp/Rge: 3-35S-10W
200 feet from S Section Line, 660 feet from E Section Line
Lease Name: YAZEL 3510 Well #: 2-3H
County: BARBER Total Vertical Depth: 4747 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		WITH 10 SX CMT
PROD	7	5541	1640	WITH 295 SX CMT
SURF	9.625	919		WITH 470 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/12/2018 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL FLORES Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 04/12/2018 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 5200'. LOAD HOLE WITH MUD & SPOT 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 960' WITH 100 SX CMT. 2ND PLUG AT 180' TO SURFACE WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8898	9154		
8528	8820		
8130	8434		
7784	8075		
7408	7715		
7048	7338		
6688	7000		
6306	6590		
5928	6220		
5573	5870		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

INVOICED

MAY 08 2018

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
APR 18 2018
KCC DODGE CITY