

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-00179-00-00
Spot: NENWNWSE Sec/Twnshp/Rge: 24-31S-35W
2349 feet from S Section Line, 2296 feet from E Section Line
Lease Name: RALPH LOWE Well #: 1
County: STEVENS Total Vertical Depth: 2997 feet

Operator License No.: 34832
Op Name: SCOUT ENERGY MANAGEMENT LLC
Address: 4901 LBJ FREEWAY SUITE 300
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2770	0	WITH 1000 SX CMT
SURF	10.75	621		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/12/2018 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TOOH WITH RODS & TBG. SET CIBP @ 2442' WITH TBG. CIRCULATE 90 BBLS MUD & CAP WITH 20 SX CMT. TOOH WITH TBG & PRESSURE TEST CASING TO 500#. RIH WITH TBG TO 1770' & SPOT 100 SX CMT. TOOH WITH TBG & PERFORATE AT 650' & CIRCULATE CMT FROM 650' TO 0'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2018 10:00 AM KCC Agent: HEITH WALSH

Actual Plugging Report:

TBG STUCK IN SAND CAN'T PULL IT. CUT AT 1762' & PUMPED 150 SX CMT PLUG. TOOH WITH TBG. SDON. 4/13/18: PRESSURE TESTED CASING TO 500# & HELD. PERFORATE AT 650'. CIRCULATED 310 SX CMT FROM 650' TO 0' FILLING THE 7" CASING & THE 7" X 10 3/4" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2492	2682		

INVOICED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CLASS C BY ORR ENTERPRISES. MAY 08 2018

Plugged through: CSG

District: 01

Signed Heith Walsh
(TECHNICIAN)

RECEIVED
APR 20 2018
KCC DODGE CITY