

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40170-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 20-33S-10E
1677 feet from S Section Line, 2319 feet from E Section Line
Lease Name: KEITH Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 1572 feet

Operator License No.: 35116
Op Name: SM OIL & GAS, INC.
Address: PO BOX 189
SKIATOOK, OK 74070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1572		50 SX
SURF	7	40		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: TOM OAST Company: _____ Phone: (620) 725-3200

Proposed
Plugging
Method:

Plug in accordance with KCC regulations and requirements.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 04/06/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1530' gelled hole and spotted 30 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" back into 900' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 147 sacks of cement were used to plug this well.

RECEIVED
KCC DIST # 3
MAY 01 2018
CHANUTE, KS

DS


INVOICED
MAY 08 2018

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)