

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04835-00-00
Spot: SWSNW Sec/Twnshp/Rge: 26-19S-14W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: OPIE Well #: 3
County: BARTON Total Vertical Depth: 3497 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3496		175 SX
SURF	8.625	796		420 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2018 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOHN THOMAS Company: THOMAS, JOHN R. DBA VAMCO O Phone: (620) 793-2604

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # hulls and 10 sx gel. Cement order was for 5 1/2" casing and when head was dug out it was found to be 4 1/2" casing. Vamco used a rig owned by them.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2018 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 770'. Ran tubing to 3410' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1395' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 50 sx cement. Pulled tubing to 300'. Circulated cement to surface on casing with 60 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 80 sx cement.

GPS: 38.36982 -098.84251

Perfs:

INVOICED
MAY 08 2018

KCC WICHITA
APR 30 2018
RECEIVED

Remarks: QUALITY WELL SERVICE

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

APR 20 2018

APR 20 2018