

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40327-00-01
Spot: NWNWNWSE Sec/Twnshp/Rge: 20-28S-4E
2525 feet from S Section Line, 2421 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 2
County: BUTLER Total Vertical Depth: 2765 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2494		100 SX
SURF		61		
SURF	8.625	206		0 SX

Well Type: EOR UIC Docket No: E20606.1 Date/Time to Plug: 01/17/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/25/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

TUBING & PACKER HUNG UP IN HOLE, CUT TUBING @ 2248', LAYED DOWN TUBING. RIH W/TUBING @ 2240', QWS MIXED & PUMPED 40 SXS 60/40 POZMIX 100# HULLS 4% GEL 2% CC. LAYED DOWN TUBING. TAGGED CEMENT PLUG @ 2060'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 256'-257' (4 HOLES). RIH W/TUBING @ 250', QWS MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL. LAYED DOWN TUBING. SWEDGED INTO 5 1/2" CASING, QWS MIXED AND PUMPED 20 SXS 60/40 POZMIX TO SURFACE, SIP # 700#.

Perfs:

Top	Bot	Thru	Comments
2124	2428	CSG	

Remarks: COMPLIANCE/ FAILED MIT

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

INVOICED
1/27/2018

JK