

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-00589-00-01

Spot: SWSNW

Sec/Twnshp/Rge: 10-26S-8E

2970 feet from S Section Line, 3630 feet from E Section Line

Lease Name: RICE

Well #: 7

County: GREENWOOD

Total Vertical Depth: 2536 feet

Operator License No.: 5697

Op Name: JACKSON BROTHERS, L.L.C.

Address: 116 E 3RD ST
EUREKA, KS 67045

	<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
--	---------------	-------------	-------------------	--------------------	-----------------

	PROD	4.5	2497		50 SX
--	------	-----	------	--	-------

	SURF	9.625	120		80 SX
--	------	-------	-----	--	-------

Well Type: EOR

UIC Docket No: E22122.1

Date/Time to Plug: 04/26/2018 8:00 AM

Plug Co. License No.: 6112

Plug Co. Name: LONG DRILLING COMPANY, LLC

Proposal Revd. from: ROSCOE G. JACKSON II

Company:

Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 4.500" casing at 2470-2420 ft. 2. 50-ft. cement plug inside and outside 4.500" at 1230-1180 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed: 04/27/2018 11:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 2466', pumped 20 sxs cement, pulled tubing to 1200', pumped 20 sxs cement, pulled tubing to 160', pumped 30 sxs cement, to surface, gel spacers between cement plugs.

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

RECEIVED
KCC DIST # 3
APR 30 2018
CHANUTE, KS

mtt

INVOICED
MAY 08 2018



Camp *Eureka*

15-073-00589-0001

Remarks: Safety meeting - Rig up to 2 3/4" tubing. Plugging order as follows:

20 vs @ 2461

20 sec @ 1200'

30. 515 @ 1100' to surface

70 ses total

Gel spacers between plugs

"Thank You!"

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.