

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-003-01781-00-01  
Spot: SWSWNWNE Sec/Twnshp/Rge: 8-21S-21E  
4060 feet from S Section Line, 2440 feet from E Section Line  
Lease Name: KOONTZ Well #: 1 SWD  
County: ANDERSON Total Vertical Depth: 1400 feet

Operator License No.: 30626  
Op Name: KITTLE, DONALD R. DBA KITTLE OIL  
Address: 708 W 8TH AVE  
GARNETT, KS. 66032

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1100		165 SX
SURF	10	30		12 SX

Well Type: SWD UIC Docket No: D25609.0 Date/Time to Plug:  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Revd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY, Phone: (620) 431-4137

Proposed Pump cement through pipe from bottom to surface. Pressure cement into casing. Top of well  
Plugging  
Method:

Plugging Proposal Received By: RYAN DULING WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/19/2018 10:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Perforated well around 600' and again at 150'. Ran 1" down the inside of the 4.5" casing to TD. Pumped cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled 1" pipe out of the casing and topped the well off with cement. A total of 176 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
APR 25 2018  
CHANUTE, KS

RD


INVOICED  
MAY 08 2018

Remarks: PLUGGED DUE TO A FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)