

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-10020-00-01
Spot: SENWSESW Sec/Twnshp/Rge: 29-30S-33W
663 feet from S Section Line, 3319 feet from E Section Line
Lease Name: VICTORY LANSING A UNIT Well #: 101W
County: HASKELL Total Vertical Depth: 6680 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4090		WITH 10 SX CMT
CIBP		4155		
CIBP		4185		
PROD	5.5	4705	1811	WITH 300 SX CMT
SURF	8.625	1796		WITH 690 SX CMT

Well Type: EOR UIC Docket No: E27509.1 Date/Time to Plug: 04/11/2018 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4100' WITH 2 SX CMT. PLUG AT 1830' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2018 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4090' WITH 10 SX CMT. 1ST PLUG AT 2934' WITH 20 SX CMT. 2ND PLUG AT 1834' WITH 50 SX CMT. 3RD PLUG AT 672' WITH 50 SX CMT. 4TH PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4160	4166		
4140	4150		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

INVOICE
MAY 08 2018

District: 01

RECEIVED
APR 16 2018
KCC DODGE CITY

Signed

Kenny Sullivan
KAS

(TECHNICIAN)