

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-25897-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 18-30S-18E
2475 feet from S Section Line, 3795 feet from E Section Line
Lease Name: BAILEY Well #: 1-SWD
County: NEOSHO Total Vertical Depth: 1404 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1404		235 SX
SURF	8.625	20		6 SX

Well Type: SWD UIC Docket No: D28101.0 Date/Time to Plug: 03/28/2018 11:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMESON Company: RIVER ROCK OPERATING Phone: (405) 606-7481

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 03/28/2018 11:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 2.375" cement string was ran to 1400' and the well pumped full of cement that contained cottonseed hulls. The cement string was pulled to 700' and the well again pumped full of cement. The cement string was pulled and the well topped off. According to operator, the well was plugged with 129 sacks of portland cement. The well was cut off below plow depth and the location restored.

Top	Bot	Thru	Comments
1381	1404		

RECEIVED
KCC DIST #3
MAY 02 2018
CHANUTE, KS

AD

INVOICED

MAY 08 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)