

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23988-00-01
Spot: NENESENW Sec/Twnshp/Rge: 24-20S-24W
3958 feet from S Section Line, 2687 feet from E Section Line
Lease Name: LEHNER, R.V. #18 Well #: 18
County: NESS Total Vertical Depth: 4530 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4320		WITH 2 SX CMT
DVT		1831		WITH 285 SX CMT
PROD	5.5	4530	0	WITH 170 SX CMT
SURF	8.625	315		WITH 200 SX CMT

Well Type: EOR UIC Docket No: E26596.2 Date/Time to Plug: 04/26/2018 10:30 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: HUNTER HEMBREE Company: VESS OIL CORPORATION Phone: (620) 791-7109

Proposed Plugging Method: CIBP @ 4350' WITH 2 SX CMT. RUN TBG TO 1900' & CIRCULATE TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2018 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4320' WITH 2 SX CMT. RAN TBG TO 2000'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT. TOP OFF 4 1/2" CASING WITH 20 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS & PRESSURE TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4372	4374		


INVOICED
MAY 08 2018

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAY - 3 2018
KCC DODGE CITY

SA