

4-061175

1-8

0001

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-24,596-A  
SE NE NW /4 SEC. 28, 20 S, 11 W  
4290 feet from S section line  
2970 feet from E section line

Operator license# 30305  
Operator: Partners in Crude  
Address: % Joe Barlet  
P.O. Box 2069  
Ponca City, OK 74602

Lease: Hagen Well # 1 OWWO  
County: Barton 112.13  
Well total depth 3450 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 268 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service, Inc. License# 31925

Address: 249 Beth Dr. - Sterling, Kansas 67579

Company to plug at: Hour: 9:30 A.M. Day: 8 Month: January Year: 1999

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service, Inc. Phone: 316-727-3410

Were: Order 200 sxs 60/40 posmix - 10% gel with hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour 1:00 P.M., Day: 8, Month: January, Year: 1999

Actual plugging report: 8 5/8" to 268' w/225 sxs. 5 1/2" to 3360'. Sanded to 3009'. Spotted 5 sxs cement on top of sand with dump bailer. Shot casing loose at 2825' and pulled to 1325'. Mixed and pumped 95 sxs cement with 300# hulls. Pulled casing to 550' and pumped 40 sxs cement with 100# hulls. Pulled casing to 250' and circulated cement to surface with 55 sxs and 100# hulls. Pulled casing and topped with 10 sxs cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD   
Bottom plug(in place): YES , CALC , NO   
Plugged through TUBING , CASING   
Anhy.plug: YES  NO   
Dakota plug: YES   
Elevation: 1778 GL

I did[  ] / did not[  ] observe the plugging.

[Signature]  
P.H. (agent)  
Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION

JAN 12 1999

CONSERVATION DIVISION  
Wichita, Kansas

1-15-99  
60549/10550

1-8 AUG 27 1999