

1-13

6 031223

API NUMBER 15- 009-24,352.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2 NW NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

, SEC. 28, T 20 S, R 11 W/E

4620 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5702

Lease Name Miller Hagen Trust 1

Operator: Pendleton Land and Expl
Name: H and C Oil Operation
Address: 401 N. Broadway
Plainville, Ks. 67663

County Barton 115.38

Well Total Depth 3550 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address Great Bend, Ks.

Company to plug at: Hour: _____ AM Day: 13 Month: Jan Year: 19 89

Plugging proposal received from Craig Christopher

(company name) Allen Drilling (phone) _____

were: 8 5/8" set at 250' w/175 sks. Circ Hole w/no less than 36 vis. mud w/no

loss or gain of fluid; Balance plugs w/mud, keep hole full. Order 200 sks 60/40 Poz 6% Gel
3% Cal Cl . Halliburton Cement Co. Fresh Water Supply Well.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:15AM Day: 13 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Spot cement plugs w/drill pipe at 3339' w/25 sks

550' w/100 sks w/Hulls

300' w/40 sks

40' w/10 sks

15 sks in rathole

10 sks in water well.

Remarks: Anhy 536' - 45' Elev. 1783' Arb 3339'
(if additional description is necessary, use BACK of this form.)

I () did not observe this plugging.

INVOICED

DATE 2-02-89

INV. NO. 23832

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow