

To be filed with State

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-009-24546.0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. Holl Company OPERATORS LICENSE NO. 5056

ADDRESS 6427 East Kellogg, P. O. Box 780167
Wichita, Kansas 67278-0167 PHONE # (316) 684-8481

LEASE (FARM) Doll WELL NO. 1-35 WELL LOCATION C W/2 NW SW COUNTY Barton

SEC. 35 TWP. 20S- RGE. 11W (E or W) TOTAL DEPTH 3430' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 267 KB CEMENTED WITH 225 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Filled hole with heavy mud; plugged with

25 sacks to top of Arbuckle, 90 sacks at 510'; 40 sacks at 310'; 10 sacks at 40' to surface.

15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain) _____

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 1993

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5:00 AM, 2-27-93

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 6055-101 et. seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Vaughn Thompson PHONE # (316) 278-2131

ADDRESS P. O. Box 129
Sterling, Kansas 67579-0129

PLUGGING CONTRACTOR STERLING DRILLING COMPANY LICENSE NO. 5142

ADDRESS P. O. Box 129
Sterling, Kansas 67579-0129 PHONE # (316) 278-2131

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Leonard D. Detter
(Operator or Agent)
Leonard D. Detter, Treasurer

DATE: March 2, 1993

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

March 1, 1993

SAMPLE LOG-----Doll #1-35
located 65' South of C-W/2 NW-SW, Section 35, T20S-R11W,
Barton County, Kansas.

OWNER: F.G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling CompanyCOMMENCED: February 19, 1993COMPLETED: February 27, 1993

TOTAL DEPTH: 3430' K.B. Driller
3430' K.B. Logger

LOG

| | |
|---------------|---------------------|
| 0' - 190' | Surface Soil & Sand |
| 190' - 507' | Red Bed |
| 507' - 524' | Anhydrite |
| 524' - 1585' | Shale |
| 1585' - 3430' | Lime & Shale |

CASING RECORD

Spud at 7:45 a.m. 2-19-93,
Drilled 270' of 12½" hole, ran
6 joints of 8 5/8" 23# New
casing, 255.56' pipe set at 267'
K.B. cemented with 225 sacks
of 60x40 pozmix with 2% Gel &
3% CC, Plug down at 11:45 a.m.
2-19-1993 by HOWCO, Good returns
to surface.

DEVIATION SURVEYS

1 3/4° - 3170'

PLUGGED & ABANDONED

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 1993
CONSERVATION DIVISION
WICHITA, KS