

15.009.24559.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 009-24,558-0000

LEASE NAME Do11 "A"

WELL NUMBER 1-35

1650' Ft. from S Section Line

495' Ft. from E Section Line

SEC. 35 TWP. 20 RGE. 11W (W)

COUNTY Barton

Date Well Completed 8-25-93
11:45 PM

Plugging Commenced 8-24-93

4:00 AM
Plugging Completed 8-25-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167
Wichita, Kansas 67278-1057

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 23, 1993 (date)

by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3448'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	268.26'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill hole with heavy mud. Heavy mud to 3335' with 25 sacks; heavy mud to 490' with 25 sacks; heavy mud to 330' with 75 sacks; heavy mud to 40' with 10 sacks to surface; 15 sacks in rathole. Used 60/40 Pozmix with 6% gel and 2 sacks of Flocele.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579-0129

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, Vice President
(Address) P. O. Box 129, Sterling, KS 67579-0129

RECEIVED

KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 93

AUG 27 1993

Cheryl R. Davis
Cheryl R. Davis, Notary Public

My Commission Expires: 2-15-97
CONSERVATION DIVISION
WICHITA, KS



Form CP-4
Revised 07-87

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG - - - - - DOLL "A" 1-35

Located: 165' East of S/2 NE SE, Section 35-20S-11W,
Barton County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 17, 1993

COMPLETED: August 25, 1993

TOTAL DEPTH: 3448'

LOG

0 - 195 Surface Soil and Sand
 195 - 285 Red Bed
 285 - 572 Red Bed - Shale
 572 - 1400 Shale
 1400 - 3448 Lime and Shale

CASING RECORD

Spud at 7:00 AM, 8-17-93. Drilled 285'
 of 12 1/4" hole. Ran 6 joints 3 5/8", 24#
 casing. 263.26' pipe set at 280' K.B.
 Cemented with 225 sacks 60/40 Pozmix,
 2% gel and 3% cc. Plug down at 10:30
 AM, 8-17-93, by Allied.
 Plugged.

Deviation Surveys: 1/2° at 285'
 2° at 3120'
 2° at 3160'
 1° at 3232'
 2° at 3339'

RECEIVED
 KANSAS CORPORATION COMMISSION

AUG 27 1993

CONSERVATION DIVISION
 WICHITA, KS