

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

PAWNEE County. Sec. 5 Twp. 20 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. C SW NW

Lease Owner C-G DRILLING CO.

Lease Name MILLER #1 Well No.

Office Address 1107 UNION NATIONAL BLDG.,

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed SEPT. 24, 1968 19

Application for plugging filed SEPT. 23, 1968 19

Application for plugging approved SEPT. 23, 1968 19

Plugging commenced SEPT. 23, 1968 19

Plugging completed SEPT. 24, 1968 19

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY, HAYS, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 4391' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278.70'	NONE
		RECEIVED STATE CORPORATION COMMISSION OCT 3 - 1968 CONSERVATION DIVISION Wichita, Kansas				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED WITH HEAVY MUD TO 660'.  
SET PLUG. PUT IN 70 SACKS CEMENT.  
FILLED WITH HEAVY MUD TO 270'.  
SET PLUG. PUT IN 20 SACKS CEMENT.  
FILLED WITH HEAVY MUD TO 40'.  
SET PLUG. PUT IN 10 SACKS CEMENT AND  
1 SACK HULLS.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.

Address 1107 UNION NATIONAL BLDG., WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G F GALLOWAY


(Notary Public or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G F GALLOWAY 1107 UNION NATIONAL BLDG.  
(Address)

Sworn to before me this 30th day of SEPT. 19 68

My commission expires DEC. 7, 1971

Phyllis Buchanan  
PHYLLIS BUCHANAN Notary Public.



W E L L L O G

OPERATOR: C-G DRILLING CO.  
 WELL NAME: MILLER #1 LOCATION: C SW NW  
 COUNTY: PAWNEE STATE: KANSAS  
 WELL COMMENCED: SEPT. 15, 1968 WELL COMPLETED: SEPT 24, 1968  
 ELEVATION: 2228 KB TOTAL DEPTH: 4391'  
 PRODUCTION: DRY AND ABANDONED RIG NO: 1  
 CASING - 8-5/8": 8 jts 278.70' W/165 SACKS QUICKSET  
 5-1/2": \_\_\_\_\_

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
278	860	SHALE	3/4° 550'	
860	1060	SAND	3/4° 1220'	
1060	1424	SHALE & RED BED	3/4° 1610'	DST #1 4376-4391'
1424	1462	ANHYDRITE	1° 2580'	
1462	1890	SHALE	1 1/4° 3180'	
1890	2440	SHALE & LIME	1 1/2° 3670'	
2440	2560	LIME		
2560	3980	LIME & SHALE		
3980	4215	LIME		
4215	4265	LIME & SHALE		
4265	4385	LIME		
4385	4391	LIME & SHALE		
4391		LIME		

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 3 - 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By [Signature]

AND SWORN TO, BEFORE ME, This 30th day of SEPT., 1968.

DEC. 7, 1971

Phyllis Buchanan  
 PHYLLIS BUCHANAN - NOTARY PUBLIC

