

STATE OF KANSAS
STATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-5-117

API NUMBER 15-145-20,201

15.145.20201.0000

LEASE NAME Isaac

RECEIVED
FEB 05 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

WELL NUMBER 4

4620 Ft. from ^N Section Line

1980 Ft. from E Section Line

SEC. 5 TWP. 20S RGE. 20W (E) or (W)

COUNTY Pawnee

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. N. #300 Wichita, Kansas 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 1-27-03

Plugging Completed 1-28-03

Is plugging proposal was approved on _____ (date)

By Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4355'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	278'	None
				5-1/2"	4341'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each. Plugged off bottom with sand to 4290' and 5 sacks cement. Ran in 1410' of 2-3/8" tubing, pumped 40 sacks common w/3% cc. displaced to balance. Pulled tubing out, shot 5-1/2" casing @670', hooked onto 5-1/2" and pumped 140 sacks cement. Max. Press. 800#. Pumped 35 sacks cement down annulus. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 2003

[Signature]
Notary Public

My Commission Expires:

