

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-135-24153-0000

LEASE NAME Roger Hinnergardt

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 12 TWP. 20 RGE. 21 ~~NE~~ or (W)

COUNTY Ness

Date Well Completed 9-14-01

Plugging Commenced 9-14-01

Plugging Completed 9-14-01

RECEIVED

NOV 06 2001

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KCC WICHITA
Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th St., Newton, KS 67114-8827

PHONE#(316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-14-01 (date)

by KCC District #2 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Miss. Depth to Top _____ Bottom _____ T.D. 4383'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	630'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Run in with plugging stands, D.P. at 1470', pump 5 bbl. #20 spacer, 50 sacks 60/40 pozmix, 6% gel, 1# floccle, 2 bbl H2O spacer, 15 bbl mud to balance, plug down pull to 660', pump 5 bbl, H2O spacer, 50 sacks cement, 2 bbl, H2O spacer, 3 bbl, mud to balance, pull D.P. out of hole, push plug down 40' solid bridge, lay down rat hole, pump 10 sacks 40' to surface, plug rat hole-15 sacks cement, plugging complete.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF KANSAS COUNTY OF HARVEY, ss.

Palomino Petroleum, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 4924 SE 84th St., Newton, KS 67114-8827

SUBSCRIBED AND SWORN TO before me this 5th day of November, 2001

Karla K. Eilert
Notary Public Karla K. Eilert

My Commission Expires: 8-27-05



OP