


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 12 Twp. 21S Rge. (E) 21 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Hinnergardt "B" Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 23, 19 65
Application for plugging filed December 23, 19 65
Application for plugging approved December 23, 19 65
Plugging commenced December 23, 19 65
Plugging completed December 23, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4479 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	363'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 500', set plug, cemented with
25 sacks cement. Heavy mud to 300', set
plug, cemented with 25 sacks cement. Heavy
mud to 40', set plug, cemented with 10 sacks
cement to bottom of cellar. Plugged rat hole
with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1965
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th Natl Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of December, 19 65



Maxine Blackman
Maxine Blackman, Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Natl Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 12-12-65

Rotary Drilling Completed 12-23-65

LOCATION: Hinnergardt "B" No. 1, C SE NW Section 12-20-21W, Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 363' (17 jts) 8 5/8" surface casing set with 185 sacks cement.
Circulated. Completed 8:00 P.M. December 12, 1965. No oil
string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Post Rock & Clay	
100	Post Rock	C. F. S.
280	Shale & Shells	4310
310	Sand	4384
375	Shale	4389
780	Shale, Shells & Red Bed	4399
788	Blaine	4409
880	Shale	4419
1095	Sand	4479
1430	Shale, Shells & Red Beds	
1470	Anhydrite	
1940	Shale & Shells	Slope Test
2410	Lime & Shale	2500
2785	Lime	3000
3845	Lime & Shale	3500
4190	Lime	4000
4314	Lime & Shale	
4479	Mississippian • RTD	S. L. M.
		3875
		4120
		4392

RECEIVED
STATE CORPORATION COMMISSION

DEC 29 1965

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebits, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 27th day of December, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebits, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public