


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 30 Twp. 20S Rge. (E) 11W(W)

Location as "NE/CNW/SW" or footage from lines SE NE NE

Lease Owner L. K. Parrish

Lease Name CARRIE Well No. 1

Office Address 714 Fourth National Bank Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 24, 1966

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced July 24, 1966

Plugging completed July 24, 1966

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Donald Truan)

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3372 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	247'	8-5/8"	7/18/66	----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 240 feet;
Hull Plug and 25 sacks Cement thru Drill
Pipe; Heavy Mud to 40 feet; Hull Plug and
10 sacks Cement to base of cellar; 2 sacks
in rat hole. Job completed at 4:15 A.M.

STATE CORPORATION COMMISSION
AUG 8 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.

Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Lawrence F. Gray of Sage Drilling Co., Inc. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray

500 Bitting Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 66

My commission expires November 26, 1966

Louise K. Whitted
Louise K. Whitted - Notary Public.

DRILLERS LOGCARRIE NO. 1

CASING RECORD:	COMPANY:	L. K. Parrish	DESCRIPTION:
8-5/8" @ 247'	CONTRACTOR:	Sage Drilling Co.	SE NE NE
w/200 sax cement	COMMENCED:	July 18, 1966	Sec. 30-20S-11W
TOTAL DEPTH:	COMPLETED:	July 24, 1966	Barton County, Kansas
3372'			Elevation: 1799 DF

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	205	
Shale & Red Bed	205	253	
Shale	253	546	
Anhydrite	546	568	
Shale	568	1280	
Lime & Shale	1280	2015	
Shale & Lime	2015	2725	
Lime & Shale	2725	3104	
Lime	3104	3220	
Lime & Shale	3220	3372	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 5th day of August, 1966.

Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.