

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 30 Twp. 20 Rge. (E) 11 (W)

Location as "NE/CNW&SW&W" or footage from lines SW NW NE

Lease Owner C. E. Denman

Lease Name Hagen Well No. 1

Office Address 3115 Broadway, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed _____ 19__

Application for plugging filed November 21 1963

Application for plugging approved _____ 19__


Plugging commenced December 3 1963

Plugging completed December 6 1963

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3420 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	245	8 5/8"	245	none
		0	3419	5 1/2"	3419	2451.03

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand back to 3400' and dump 5 sacks of cement.
Push plug to 235'. Sand back to 220' and dump 2 sacks of calseal.
Bail hole down to 205'. Dump 25 sacks of cement. Fill with mud to 30' and cap with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Ellinwood, Kansas

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 63

My commission expires July 7, 1964

[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

WELL LOG

NOV 22 1963

DENMAN & ASSOCIATES, HAGEN #1
SW NW NE Section 30-20-11
Barton County, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Figures indicate bottom of formation:

ELEVATION: 1814 KB

PIPE RECORD:

8 5/8" set at 245' with
185 sacks of cement.
5 1/2" set at 3419 with
125 sacks of cement.

0	to	10	cellar
		150	shale & sand
		340	shale
		635	shale & red bed
		1395	shale & shells
		2100	lime & shale
		2675	shale & shells
		3360	lime & shale
		3420	Rotary Total Depth

ROTARY COMMENCED: July 22, 1963

ROTARY COMPLETED: July 31, 1963

GEOLOGICAL TOPS:

Heebner	2982
Brown Lims	3114
Lansing	3128
Arbuckle	3354
5 1/2" casing	3419
Total Depth	3420

I, Richard Hogg, Drilling Superintendent for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Richard Hogg
Richard Hogg

Subscribed and sworn to before me this 6th day of August, 1963.

George A. Meyer
George A. Meyer