

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required A...
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

Strike out upper line
when reporting plug-
ging off formations.

Barton County. Sec 30 Twp 20 Rge 11 ~~W~~ W (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE SE NW

Lease Owner. Robert L. Williams

Lease Name. Soeken "B"

Well No. 1

Office Address. 406 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 8, 1948

Application for plugging filed November 9, 1948

Application for plugging approved November 9, 1948

Plugging commenced November 10, 1948

Plugging completed November 29, 1948

Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. C. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3416 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	265	None
				5-1/2"	3415'	2391'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled Hole with Chat 3129 to 2925'
Five Sacks Cement from 2925' to 2905'
Mudded Hole from 2905' to 250'
Rock Bridge from 250' to 240'
Fifteen Sacks cement for 240' to 200'
Filled with mud from 200' to 10'
Five sacks cement from 10' to Bottom of Collar.

1-26-1949
RECEIVED
CONSERVATION DIV.
JAN 26 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Robert L. Williams
Address 406 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Robert L. Williams (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Robert L. Williams

406 Union National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of January, 1949

My commission expires October 31, 1951

Charles J. Roberts
Notary Public.



WELL LOG

R. L. Williams
Soeken "B" #1

Sec. 30- T.20S- R.11W
SE/4 SE/4 NW/4
County: Barton

Total Depth - 3415'
Comm: 10-12-48 Comp.: 10-24-48
Contractor: J.D.Ferrell Drilling Co., Inc.
Issued: 10-25-48 Rotary: O-3415

Elevation: 1812'
Production:

Casing: 8 5/8" - 265' Cemented with 150 Sax Bulk
Cement. Cement Circulated
5 1/2" - 3414' Cemented with 150 Sax Bulk
Cement.

Figures Indicate Bottom of Formations.

cellar	5
clay, sand, shale	200
shale & shells	265
shale & red bed	580
anhydrite	600
shale & shells	1480
sand	1505
broken lime	1645
lime	1735
lime, sand, & shale	1925
lime	2035
broken lime	2105
lime & shale	2785
lime	3030
lime & shale	3137
lime	3381
lime & conglomerate	3415
Total Depth	3415

Tops:	
Anhydrite	580
Topeka	2726
Heebner	2998
Lansing	3133
Conglomerate	3379
Total Depth	3415

8420 06 130

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

J.D.FERRELL DRILLING COMPANY, INC.

By: J.W. Galbraith

Subscribed and sworn to before me this 29 day of Oct 1948

My commission expires: 10-15-51

Merle V. Suedeyser
Notary Public

RECEIVED
JAN 26 1949
STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
SEC 30 T 20 R 11W
PAGE 67 LINE 38