


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County. Sec. 30 Twp. 20 Rge. II W(E)      (W)  
Location as "NE/CNW&SW" or footage from lines Sec SW  
Lease Owner V. E. Wiggins  
Lease Name Soaken Well No. I  
Office Address P.O. Box 191 Mc Pherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 12-31- 1947  
Application for plugging filed Feb 1964  
Application for plugging approved Feb 1964  
Plugging commenced Feb 19 1964  
Plugging completed Feb 27 1964  
Reason for abandonment of well or producing formation Went dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production      19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation      Depth to top      Bottom      Total Depth of Well 3396' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,076'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3396' to 3370'. Dumped 5 sx of cement. Mudded hole to 300'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

3-9-1964

RECEIVED  
STATE CORPORATION COMMISSION

MAR 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 Kings Dr. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 th day of February, 1964

My commission expires January 5, 1966

Judy Lamb Notary Public.


OWNERSHIP

Company R. L. WILLIAMS Transferred to: V.E. Wiggins SEC. 30 T. 20 R. 11E  
Farm Soeken No. 1 SEc S7

Total Depth 3396'  
Com. 12-18-47  
Date of Test:  
Contractor:  
Issue 1-24-48

Comp. 12-31-47

County Barton  
KANSAS



CASING:

8-5/8" 310' Cem. 7/200 Sx.  
5-1/2" 3382' Cem. 7/200 Sx.

Flow: \_\_\_\_\_

Production Pot 994 Bbls.

Figures indicate Bottom of Formations.

sand	125
sand & clay	225
clay & shale	300
shale & shells	555
shale shells redbed	540
shale & shells	1475
shale & lime	1590
lime	1645
lime & shale	1620
lime	1390
lime & shale	1995
shale	2171
lime & shale	2346
shale & shells	2520
lime & shale	2710
lime	2995
lime & shale	3250
no formation	3320
lime & shale	3396

Total Depth

3396

TOPS:

Brown Lime	3142
Lansing	3158
Simpson Shale	3573
Arbuckle	3301

3396 40

RECEIVED  
STATE CORPORATION COMMISSION

MAR 9 1948

CONSERVATION DIVISION  
Wichita, Kansas

Conn 2 - 19.64

Comp - 2 - 27 - 64

300 - 290 - 250

35 - 30 - 20