

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 30 TWP. 20 RGE. 11 E/W  
Location as in quarters or footage from lines:  
100' E of SW NE SW


Lease Owner Petroleum Energy, Inc.  
Lease Name Soeken Well No. 1  
Office Address 415 First Nat'l Bk. Bldg. Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed 3-24-83  
Application for plugging filed 3-24-83  
Plugging commenced 3-25-83  
Plugging completed 3-25-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3427

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug: 3380' w/20 sacks cement thru drill pipe  
Next Plug: @ 580' w/20 sacks " " " "  
Next Plug: @ 300' w/75 " " " "  
Top Plug: @ 40' w/10 sacks cement  
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Pete Musgrove (employee of owner) or (~~owner or operator~~) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) *Pete Musgrove*  
Box 823 Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of March, 1983

*Allegre*  
Notary Public.

My Commission expires: 4-29-86

APR 01 1983

CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: March 17, 1983  
 DATE COMPLETED: March 25, 1983

Petroleum Energy, Inc.  
 SOEKEN #1  
 100' E of SW NE SW  
 Sec. 30, T20S, R11W  
 Barton County, Ks.

ELEVATION: 1812 G.R.

0 - 2722' Surface Soil, Sand, Shale  
 2722 - 2989' Lime  
 2989 - 2992' Shale  
 2992 - 3005' Lime & Shale  
 3005 - 3123' Lime  
 3123 - 3367' Lime & Shale  
 3367 - 3427' Dolomite  
 3427' RTD

FORMATION DATA

Topeka	2722'
Heebner	2989'
Toronto	3005'
Br. Lime	3123'
Lansing	3137'
Arbuckle	3367'
RTD	3427'

Surface Pipe: Set new 8-5/8"  
 @ 250' w/200 sacks common,  
 2% gel 3% cc.

## A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON) ss

Pete Musgrove of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 30 day of March 1983.

My Comm. Expires:

4-29-86

Dorothy M. Hague  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

APR 01 1983

CONSERVATION DIVISION  
 Wichita, Kansas