


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County, Sec. 30 Twp. 20 Rge. (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW, SW, NW.
Lease Owner **Aledo Oil & Gas Co., Inc.**
Lease Name **Soeken #1** Well No. _____
Office Address **Wichita, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry hole**
Date well completed **7-11-49** 19____
Application for plugging filed **8-29-49** 19____
Application for plugging approved **8-3-49** 19____
Plugging commenced **August 29, 1949** 19____
Plugging completed **~~August~~ Sept 2, 1949** 19____
Reason for abandonment of well or producing formation **dry**



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **C. Stough**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **3403** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
K.C.	Water	3142	3232	5 $\frac{1}{2}$	3383	1620'
Arbuckle	water	3379	3403			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Arbuckle plugged with Lane well plug at 3265
Rocked hole from 3225' to 3140'. Run 5 sacks of cement
~~XX~~
~~XX~~
Mudded hole to 315'. Run 15 sacks of cement.
Mudded hole to 35'. Run 10 sacks of cement.
Well Completed.

9-10-49
RECEIVED
Conservation Div.
SEP 10 1949
STATE CORPORATION COMMISSION
KANSAS


(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to **Aledo Oil & Gas Co., Inc.**
Address **Wichita, Kansas**

STATE OF Kansas, COUNTY OF Barton, ss.
Aledo Oil & Gas Co., Inc. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock

SUBSCRIBED AND SWORN to before me this 8th day of September, 1949

My commission expires June 13, 1951
Notary Public.



ALEDO OIL AND GAS CO. INC. AND TRANSIT CORPORATION

SOEKEN #1
 SW/4 NW/4, Section 30-2-S-11W
 Barton County, Kansas

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	100	
Clay & shale	100	150	
Shale & red bed	150	260	
Shale & shells	260	315	8 5/8" C.S.A. 315', W/200 sacks cement
Red bed & shale	315	485	
Shale & shells	485	1110	
Salt	1110	1230	
Shale & shells	1230	1500	
Lime & shale	1500	2270	
Shale & shells	2270	2495	
Shale & lime	2495	2735	
Broken lime	2735	2815	
Lime & shale	2815	2920	
Lime	2920	3125	
Lime & shale	3125	3166	
Lime	3166	3387	5 1/2" C.S.A. 3383 1/2', W/100 sacks cement
Total Depth		3387	

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

By L. J. Kruse
 L. J. Kruse, Assistant Secretary

Subscribed and sworn to before me this 29th day of July, 1949.

Nazil Turley
 Notary Public

AUG 3 - 1949
 My commission expires: March 13, 1953
 KANSAS

PLUGGING
 FILE SEC 30 T 20 R 11 W
 BOOK PAGE 12 LINE 36