

COPY

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barton SEC. 30 TWP. 20 S RGE. 11 W E/W  
 Location as in quarters or footage from lines:  
SW SW SE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Tenneco Oil Company  
 Lease Name Jutting Well No. 1  
 Office Address Box 1485 @ Great Bend, Kansas, 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole):  
 Date Well Completed 6/6/48  
 Application for plugging filed  
 Plugging commenced 7-14-82  
 Plugging completed 7-19-82  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation ARBUCKLE Depth to top 3353 bottom 3370 T.D. 3370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	580'	None
				5-1/2"	3353'	1354'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom was plugged off - Ran in baler and drove bridge to 1810'. Sanded back to 1750' and ran 5 sacks cement.  
Pumped 3 sacks hulls, 25 sacks cement and 1 sack hulls down surface, gel started to circulate out surface, ran tubing to 300', circulated 110 sacks cement, pulled tubing out and capped well with 15 sacks cement.  
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
 Box 347 Chase, Kansas, 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day of October, 19 82

My Commission expires:



[Signature] Notary Public.  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 OCT 22 1982

JUNE 8, 1948  
DRILLING LOG

15.009.14770.0000

Bay Petroleum Company  
Brown Building  
Wichita, Kansas

Lease: Jutting #1

County: Barton, Kansas  
Sec: 30-20-11W  
Location: Center of SW/4 of SW/4  
of SE/4

Rotary Total Depth: 3355'  
Comm: 5/25/48 Comp: 6/6/48  
Shot or Treated  
Casing: 8 5/8" @ 580' 5 1/2" @ 3353'

Contractor: Gabbert & Lindas Drilling Company, Inc.  
1314-16 Union Nat'l Bank Building  
Wichita, Kansas

Figures Indicate Bottom of Formations:

0.	To	212	Sand
212		245	Shale & Shells
245		555	Red Bed, Shale & Shells
555		570	Red Bed
570		580	Anhydrite
580		595	Lime
595		1055	Red Shale
1055		1115	Shale
1115		1240	Salt & Shale
1240		1475	Shale & Shells
1475		1570	Lime
1570		1800	Lime & Shale
1800		2000	Lime
2000		2185	Shale
2185		2330	Shale & Lime
2330		2580	Lime & Shale
2580		2660	Lime
2660		2765	Lime & Shale
2765		3015	Lime
3015		3064	Lime & Shale
3064		3090	Lime
3090		3160	Shale & Lime
3160		3355 T.D.	Lime

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1948  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

I, the undersigned, being duly sworn on oath state that the above statement and log is true and correct record and log of the well drilled at the location above described.

ga GABBERT & LINDAS DRILLING COMPANY, INC.

By: Scott Stucky

Subscribed and sworn to before me this 8th day of June, 1948.

Catherine Darcy  
NOTARY PUBLIC

My commission expires March 25, 1952

JUNE 8, 1948  
DRILLING LOG

15.009.14770.0000

Bay Petroleum Company  
Brown Building  
Wichita, Kansas

Lease: Jutting #1

County: Barton, Kansas  
Sec: 30-20-11W  
Location: Center of SW/4 of SW/4  
of SE/4

Rotary Total Depth: 3355'  
Comm: 5/25/48 Comp: 6/6/48  
Shot or Treated  
Casing: 8 5/8" @ 580' 5 1/2" @ 3353'

Contractor: Gabbert & Lindas Drilling Company, Inc.  
1314-16 Union Nat'l Bank Building  
Wichita, Kansas

Figures Indicate Bottom of Formations:

O.	To		
	212	Sand	
212	245	Shale & Shells	
245	555	Red Bed, Shale & Shells	
555	570	Red Bed	
570	580	Anhydrite	
580	595	Lime	
595	1055	Red Shale	
1055	1115	Shale	
1115	1240	Salt & Shale	
1240	1475	Shale & Shells	
1475	1570	Lime	
1570	1800	Lime & Shale	
1800	2000	Lime	
2000	2185	Shale	
2185	2330	Shale & Lime	
2330	2580	Lime & Shale	
2580	2660	Lime	
2660	2765	Lime & Shale	
2765	3015	Lime	
3015	3064	Lime & Shale	
3064	3090	Lime	
3090	3160	Shale & Lime	
3160	3355 T.D.	Lime	

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

I, the undersigned, being duly sworn on oath state that the above statement and log is true and correct record and log of the well drilled at the location above described.

ga GABBERT & LINDAS DRILLING COMPANY, INC.

By: Scott Sturkey

Subscribed and sworn to before me this 8th day of June, 1948.

Catherine Dancy  
NOTARY PUBLIC

My commission expires March 25, 1952