

LEASE NAME Wheeler B

WELL NUMBER #2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1980 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR J. Mark Richardson

SEC. 28 TWP. 30 RGE. 19 (X or W)

ADDRESS 640 Century Plaza Bldg., Wichita, Ks 67202

COUNTY Kiowa

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Date Well Completed _____

Character of Well Oil

Plugging Commenced 3-7-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-11-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 4693 Bottom 4697 T.D. 4760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	<u>641</u>	<u>8 5/8</u>	<u>641</u>	<u>0</u>
		Product		<u>4 1/2</u>	<u>5079</u>	<u>2316</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
plug back depth 4760, sand off to 4600; dump 4 sk cement; pull 2316 4 1/2 casing.
Top plugs 4 sx hull; 10 gel; 50 sx cement; 10 gel 1 hull; 8 5/8 plug; 150 sx cement.
Cement 60/40 w/60% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Greensburg Well Service License No. _____

Address Box 632, Greensburg, KS 67054

STATE OF Kansas COUNTY OF Sedgwick, ss.

J. Mark Richardson

(~~Employer or Operator~~) of Wheeler B of Wichita, Kansas above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson

(Address) 640 Century Plaza Bldg.

Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 88

Kim Santella
 Notary Public

My Commission Expires: _____



GABBERT JONES, INC.
WHEELER DRILLERS
DRILLERS' WELL LOG

Wheeler "A-2"
NW-SW Sec. 28-308-19W
Kiowa County, Kansas

Commenced: 7-26-82

Completed: 8-7-82

OPERATOR: JAMES RICHARDSON

From	Depth	Formation	Remarks
0	641	Sand-Redbed	
641	1360	Redbed-Shale	Ran 15 jrs of 2 1/2" 8 5/8" csg set @ 637' Cemented w/ 400 sks Common 2% Gel
1360	2080	Shale-Shells	12 CC PD @ 3:00 a.m. 8-27-82
2080	2730	Shale	
2730	3230	Shale-Lime	
3230	3680	Lime-Shale	
3680	5080	Lime	Ran 128 jrs of 10 1/2" 4 1/2" csg set @ 5079' Cemented w/ 200 sks 60/40 Pasmix 2% Gel 10% Salt PD @ 12:00 p.m. 8-7-82
	5080	TD	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, certify that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT JONES, INC.

James Richardson
JAMES RICHARDSON

Subscribed and sworn to before me this 12th day of August, 1982.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS, NOTARY PUBLIC

My Commission expires February 6, 1983.