


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 27 Twp. 20S Rge. 11W(E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Hagen "B" Well No. 1
Office Address 1100 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 7, 1956 19
Application for plugging filed November 7, 1956 19
Application for plugging approved November 7, 1956 19
Plugging commenced November 7, 1956 19
Plugging completed November 7, 1956 19
Reason for abandonment of well or producing formation Non-productive

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3352 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to 180 feet
1/3rd sack hulls and solid plug and 20
sacks cement mud to 35 feet;
1/3rd sacks hulls, solid plug and 10 sacks
cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1100 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 56

My commission expires August 10, 1957
[Signature] Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
NOV - 9 1956
PLUGGING
FILE T-SEC-27 T-20 R-11W
BOOK PAGE 114 LINE 23

11-9-56

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: October 29, 1956

Contractor: Quaker Drilling Co., Inc.

Completed: November 7, 1956

Hagen "B" No. 1
SE SW SW Sec. 27-20S-11W
Barton County, Kansas

Elevation: 1785 K.B.

Production: D & A

Casing Record:

Set 205' of 8 5/8" casing with 225 sacks pozmix

(Figures Indicate the Bottom of Formations)

<u>FORMATIONS</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	145	Anhydrite	525
Shale & Shells	205	Heebner	2952 -1167
Red Bed	525	Brown lime	3075 -1290
Anhydrite	550	Lansing	3095 -1310
Red Bed	1185	Arbuckle	3343 -1558
Shale & Shells	1475	Rotary Total Depth	3352 -1567
Lime & Shale	2650		
Shale	2725		
Lime	2760		
Lime & Shale	3270		
Lime	3329		
Lime & Shale	3352		

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE SW SW of Section 27, Township 20 South, Range 11 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: *Dwight Jensen*

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1956.

Virginia Mundell
Notary Public

MY COMMISSION EXPIRES:
August 10, 1957.

RECEIVED
STATE CORPORATION

CONSERVATION

PLUGGING

FILE SEC. 27 T. 20 R. 11W
BOOK PAGE 114 LINE 23