

15-009-21383-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas
API Number 15 - 009-21,383-0000 (of this well)

Operator's Full Name Shields Oil Producers, Inc

Complete Address Shields Bldg. Russell, Kansas 67665

Lease Name Deutch "B" Well No. 1

Location N/2 S/2 SW Sec. 10 Twp. 16 Rge. 13 (E) (W) X

County Barton Total Depth 3374'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor Shields Drlg. Co., Inc. & Allied Cementing Co.

Address Shields Bldg. Russell, Kansas 67665 License No. _____

Operation Completed: Hour 6:30 AM Day 18m Month 5 Year 1978

The above well was plugged as follows:

- _____ Filled hole with mud and spotted 50 sx cement at 500'.
- _____ Filled hole with mud and spotted 25 sx cement at 240'.
- _____ Filled hole with mud to 40' and 1/2 sx hulls, plug, and
- _____ 10 sx cement to bottom of celler.
- _____ 2 sx cement in rat hole.
- _____ 2 sx cement in mouse hole.
- _____ 262' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5-22-78

INV. NO. 7336-U