

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3
Rev. 1-8-82

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1982
CONSERVATION DIVISION
WICHITA, KANSAS
3-23-82

API Number 15-097-20,8

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dave Thomas Jr.

Complete Address P.O. Box 2026 Farmington New Mexico 87401

Lease Name Brensing Well No. 1

Location 723' FWL-660' FNL Sec. 8 Twp. 28 Rge. 20 (East) (West)

County Kiowa Total Depth 5050'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Santa Fe Drilling Co.

Address _____ License No. _____

Operation Completed: Hour: 11:30 AM. Day: 19 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1318'. 1st plug at 1280' with 60 bbls of cement. 2nd plug push rubber plug to 660' and pumping 35 bbls of cement on top of it. 3rd plug on solid bridge at 40' to 50' with 10 bbls of cement. Then they circulated 10 bbls of cement in rat hole & 5 bbls of cement in mouse hole. The cement was pumped down through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.

Amount of Surface Casing: 678' of 8 5/8" surface casing cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was not on location when well was plugged but I feel it was plugged this way. I went by location this A.M. and the pusher told me it was plugged as stated.

Signed: Paul A. Luther
Conservation Division Agent

INVOICED

DATE 3-26-82

INV. NO. 9767-W

STATE OF KANSAS

15-097-20865-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

March 26, 1982

INVOICE NUMBER: 9767-W

TO: Dave Thomas Jr.
Box 2026
Farmington New Mexico 87401

PAYABLE UPON RECEIPT

PLUGGING ASSESSMENT AS FOLLOWS:

Breasing #1
723' FWL 660' FNL Sec. 8-28-20W
Kiowa
5050' \$164.13

NOTE: We also need the following before our file is completed:


- X _____ Well Plugging Record (CP-4)
- X _____ Well Log
- X _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



Administrator

Mr. Paul Luthi Box 495 Minneola Ks. 67112 (316) 885-4838

is hereby assigned to supervise the plugging of the above mentioned well.